



# Quote

# Q-TAL-2026-903


**TAL Trucks Consultancy FZE**

Al Shmookh Business Center M 1003  
 One UAQ, UAQ Free Trade Zone  
 Umm Al-Quwain Umm al-Quwain  
 U.A.E  
 TRN 104020735700003  
 971-50-112-7792  
 info@taltrucks.com  
 www.tal-trucks.com

Quote Date : 08 Jul 2026  
 Expiry Date : 01 Sep 2026  
 Reference# : USED HINO FOOD TRUCK

Bill To  
**NEW QUOTE**




Subject :  
 USED HINO FOOD TRUCK - DRIVABLE



#	Item & Description	Qty	Rate	Taxable Amount	Tax	Amount
1	USED HINO 300 916 CHASSIS - Units will between 100,000 - 250,000KMS (2017 - 2022) - depends on best value. All vehicle will be inspected by professional team, oil change, fluid changed, motor inspection and transmission inspection.	1.00	84,999.00	84,999.00	4,249.95 5.00%	89,248.95
2	 TAL 50+ Point Inspection Certificate 50-POINT INSPECTION CHECKLIST (For all that applies)  1. General & Documentation  Verify chassis number, engine number, and registration documents Confirm model and year of manufacture Check Odometer reading	1.00 pcs	1.00	1.00	0.05 5.00%	1.05



#	Item & Description	Qty	Rate	Taxable Amount	Tax	Amount
	<p>(ensure below transport mileage if new)</p> <p>Review service records or warranty booklet</p> <p>Confirm all keys, manuals, and accessories are present</p> <p>2. Exterior Condition</p> <p>Inspect body panels for dents, paint defects, or corrosion</p> <p>Check doors, hood, and tailgate operation</p> <p>Inspect mirrors, headlights, tail lamps, and indicators for cracks or alignment</p> <p>Verify windscreen and windows (no cracks, chips, or scratches)</p> <p>Inspect bumpers, mudguards, and license plate brackets</p> <p>3. Chassis &amp; Frame</p> <p>Check chassis alignment (no visible bends, welds, or rust)</p> <p>Verify mounting points for the fabricated body are secure</p> <p>Inspect cross members and bolts for torque and corrosion</p> <p>Confirm underbody coating is complete and even</p> <p>4. Engine Compartment</p> <p>Check engine oil level and condition</p> <p>Inspect coolant level and radiator condition</p> <p>Verify battery health, terminals tightness, and no corrosion</p> <p>Check belts and hoses for wear, tension, and leaks</p> <p>Start engine and verify no abnormal noise, smoke, or vibration</p> <p>Confirm fuel system (no leaks, proper filtration)</p> <p>5. Transmission &amp; Driveline</p> <p>Inspect gearbox operation (smooth shifting)</p> <p>Check clutch pedal free play and engagement</p> <p>Inspect driveshaft, U-joints, and differential for leaks or vibration</p> <p>Confirm 4x2 / 4x4 system (if applicable) operates correctly</p>					

#	Item & Description	Qty	Rate	Taxable Amount	Tax	Amount
	<p>6. Suspension &amp; Steering</p> <p>Inspect front and rear suspension for leaks, damage, or looseness</p> <p>Check leaf springs, shock absorbers, and bushings</p> <p>Verify steering play and alignment</p> <p>Inspect power steering fluid level</p>					
	<p>7. Brake System</p> <p>Inspect brake pads, discs /drums, and lines</p> <p>Check brake fluid level and leaks</p> <p>Test parking brake for holding strength</p> <p>Verify ABS indicator lights function properly</p>					
	<p>8. Wheels &amp; Tires</p> <p>Inspect tire tread depth (min 5 mm for new delivery)</p> <p>Check tire pressure (match recommended PSI)</p> <p>Inspect rims for cracks, dents, or rust</p> <p>Verify wheel nut torque</p>					
	<p>9. Electrical &amp; Lighting</p> <p>Verify operation of all lights, indicators, and hazards</p> <p>Test horn, reverse buzzer, and interior lighting</p> <p>Check alternator output voltage (13.8–14.2 V at idle)</p> <p>Inspect all fuse boxes and relays for proper function</p>					
	<p>10. Cabin &amp; Interior</p> <p>Inspect dashboard, seat covers, and carpets for damage</p> <p>Verify seat belts and adjusters</p> <p>Test instrument cluster, gauges, and warning lights</p> <p>Check AC and heater operation</p> <p>Inspect windows, wipers, and washers</p> <p>Verify door locks, handles, and seals</p>					
	<p>11. Fabricated Body / Special Conversion (if applicable)</p> <p>(For Mobile Office, Salon, Food</p>					

#	Item & Description	Qty	Rate	Taxable Amount	Tax	Amount
	<p>Truck, Workshop, etc.)</p> <p>Inspect structural welds and body alignment  Verify insulation thickness (100mm PU) and finishing  Check electrical system (DB, sockets, breakers)  Test lighting, AC, and plug-in connections  Inspect cabinets, doors, flooring, and walls for proper finish  Confirm fire safety (extinguisher, smoke detector, exit signage)  Test generator inlet, solar, and CCTV systems (if installed)</p> <p>12. Road Test  Start engine and observe idle stability  Drive at different speeds (20 /40/60 km/h) to check noise and vibration  Test steering response, brake balance, and gear shift  Verify temperature gauge and warning lights remain normal</p> <p>13. Final Checks &amp; Handover  Ensure vehicle cleaned and detailed  Confirm all optional equipment installed  Attach inspection report with technician's name and signature  Capture photos/videos of finished unit for client record</p>					
3	<p>Box dimensions - 6m x 2.5m x 2.2m  ( Length x Width x Height )  Chassis reinforcement using MS - I BEAMS- UPN - RHS  TUBES - U pocket for 100mm panels installation welded onto the Base platform.</p>	1.00	94,993.00	94,993.00	4,749.65 5.00%	99,742.65
4	<p>100mm panels strong rigid constructed with aluminum / GI U beading covered with edges and corners  Front - back - roof - sides</p>	1.00	1.00	1.00	0.05 5.00%	1.05
5		1.00	1.00	1.00	0.05	1.05

#	Item & Description	Qty	Rate	Taxable Amount	Tax	Amount
	 <p><b>FLOORING:</b> Flooring: The floor system consists of a 1.5 mm thick galvanized steel (GI) base sheet, overlaid with 18 mm marine-grade plywood for structural rigidity. The top surface is finished with a 3 mm polyurea fiber-reinforced resin coating, available in grey or black color options. All perimeter joints and corner edges are treated with a waterproof sealant to ensure a seamless, hygienic, and moisture-resistant finish suitable for commercial kitchen use.</p>	pcs			5.00%	
6	 <p><b>Counter / Shelving Works</b> Worktop counter (Open style underneath) as per available space  Shelving as per available space. All made of Stainless steel.</p>	1.00 pcs	1.00	1.00	0.05 5.00%	1.05
7	 <p><b>SERVING WINDOW:</b> Provision of a service window fabricated in accordance with the approved design, comprising either a sliding or hinged configuration.  The window shall have approximate dimensions of 2.0 m (L) × 1.0 m (H) and shall be constructed with durable aluminum framing, fitted with an integrated locking handle and continuous weather-sealed edges to prevent ingress of dust, water, and pests.  Any increase in window dimensions or provision of customized window designs beyond the approved scope shall be subject to additional charges and prior approval.  Installation shall comply with applicable food safety,</p>	1.00 pcs	1.00	1.00	0.05 5.00%	1.05

#	Item & Description	Qty	Rate	Taxable Amount	Tax	Amount
	hygiene, and structural requirements of the relevant local authorities.					
8	 <p><b>ELECTRICAL SYSTEM</b> Electrical System</p> <p>The electrical installation will be designed and executed according to the equipment load requirements and approved power schedule.</p> <p>Distribution Board: Customized breaker box sized according to the total electrical capacity of all installed equipment.</p> <p>Lighting &amp; Power: Includes energy-efficient LED lighting, complete internal wiring system, industrial-grade sockets, and plugs for all service areas.</p> <p>Main Power Connection: Equipped with a Seashore plug for city power connection, compatible with external supply standards.</p> <p>Cabling &amp; Components: Uses 2.5-10 mm<sup>2</sup> gauge copper cables from Ducab, with breakers and protection devices by Hager / Schneider / ABB.</p> <p>Power Input: 3-phase supply rated at 63A incomer, with 10-15mm<sup>2</sup> armoured cabling depending on the final load schedule.</p> <p>Sockets: Standard stainless-steel surface-mounted double-pin outlets provided across work areas.</p>	1.00 box	1.00	1.00	0.05 5.00%	1.05
9	 <p><b>WATER SYSTEM</b> Supply and installation of a three-compartment stainless steel sink basin, in compliance with food safety and hygiene requirements.</p>	1.00 pcs	1.00	1.00	0.05 5.00%	1.05

#	Item & Description	Qty	Rate	Taxable Amount	Tax	Amount
	<p>Complete internal potable water piping, approved fittings, and dedicated water pump shall be provided.</p> <p>The system includes a 50-litre fresh water tank and a 55-litre waste water tank to ensure proper water supply and disposal.</p> <p>Where an existing approved water connection is available, a plug-and-play connection system shall be installed in accordance with local authority regulations.</p>					
10	 <p><b>Superior Hood / Exhaust Hood</b>  * Superior Hood / Exhaust Hood as per cooking line required (S.S. 304 2mm thickness)  - x2 Extraction Fan: Fengda:  * RPM: 2300-2600  * Airflow (cbm/h): 2000-2200  * Air Pressure: 430-450  * dB: 75-80  Size: (L2m*D60m)  (If Larger is required additional charges will apply)</p>	1.00 pcs	1.00	1.00	0.05 5.00%	1.05
11	 <p><b>2 ton Split AC unit with compressor</b>  Supply and installation of heavy-duty split air conditioning unit complete with separately mounted external compressor /condenser unit suitable for commercial container and kitchen applications.</p> <p>Cooling Capacity: 24,000 BTU  Capacity Rating: 2 Ton (2 TR)  Includes indoor unit, outdoor compressor, copper piping, drainage line, electrical connections, mounting brackets, and commissioning works  Designed to provide efficient cooling performance suitable for UAE climate conditions and continuous operational use.</p>	1.00 pcs	0.00	0.00	0.00 5.00%	0.00

#	Item & Description	Qty	Rate	Taxable Amount	Tax	Amount
			<b>Sub Total</b>	180,000.00	9,000.00	189,000.00
Items in Total 11.00				Total Taxable Amount		180,000.00
					<b>Total</b>	<b>AED189,000.00</b>

## Tax Summary

Tax Details	Taxable Amount (AED)	Tax Amount (AED)	Total Amount (AED)
Standard Rate (5%)	180,000.00	9,000.00	189,000.00
<b>Total</b>	<b>AED180,000.00</b>	<b>AED9,000.00</b>	<b>AED189,000.00</b>

## Notes

Thank you for your consideration, we look forward to executing your project.

## Terms & Conditions

### Quotation Confirmation & Invoicing

This quotation shall become contractually binding upon written acceptance by the client, issuance of an LPO, or payment of any amount toward the project, whichever occurs first. Upon confirmation, an official tax invoice shall be issued.

### Payment Terms

\* Payments shall be made strictly in accordance with the approved LPO or as otherwise agreed in writing.

Project Fabrication costing: AED 189,000.00

Truck Payment 100% upfront: AED 89,250.00

- The project payment structure consists of an advance deposit: AED 70,000.00

- Balance due upon completion of fabrication and prior to delivery or handover: AED 29,750.00

\* Failure to make payments within agreed timelines may result in suspension of work without liability to TAL Trucks Consultancy FZE.

### Project Timeline:

\* The estimated project duration is 30-50 days from receipt of deposit, approvals, and final drawings, subject to current production capacity.

\* All timelines are indicative and may be revised due to force majeure, material availability, authority approvals, client delays, or scope variations. No delay penalties shall apply.

Exclusions, Unless explicitly stated otherwise in writing, the following are strictly excluded from the scope of work:

- 1) Supply or installation of equipment, including but not limited to cooking equipment, chillers, and freezers
- 2) Transportation, delivery, positioning, or offloading of the unit at the client's site
- 3) Fire suppression or fire-fighting systems
- 4) Signage, branding, wrapping, and vinyl graphics
- 5) RTA approvals, Kitchen Committee inspections, CID approvals, or any authority approvals related to signage or wrapping

### Variations & Substitutions

\* Any variation, modification, or additional requirement requested by the client shall be subject to a formal variation order and additional cost and/or time.

\* In the event that any specified material or component becomes unavailable, TAL Trucks Consultancy FZE reserves the right to substitute it with an equivalent or superior alternative without prior notice.

### Permits, Approvals & Third-Party Costs

\* All permits, NOCs, inspections, and authority approvals are strictly under the client's scope, including but not limited to Municipality, Civil Defense, Building Management, Décor approvals, and landlord approvals.

\* Any deposits, fees, charges, or insurance premiums required by developers, authorities, or third parties are expressly excluded.

### Drawings & Submittals

\* Detailed shop drawings, layouts, and material submittals shall be prepared and submitted only after job confirmation and receipt of the required deposit.

\* Approval of drawings by the client constitutes acceptance of design, dimensions, and specifications.

### Warranty & Liability

\* A limited warranty of one (1) year applies exclusively to fabrication workmanship under normal and intended use.

- \* The warranty expressly excludes lighting fixtures, electrical components, rubber parts, consumables, and any damage resulting from misuse, negligence, improper operation, or installation/removal of equipment by the client or third parties.
- \* Any modification, alteration, or service carried out by third parties without written approval shall immediately void the warranty in its entirety.
- \* Signage and vinyl wrapping, if arranged, shall be covered solely under the third-party supplier's warranty and are excluded from the fabrication warranty.
- \* Equipment warranty if arranged, shall be covered solely under the third-party supplier's warranty and are excluded from the fabrication warranty.
- \* Fire Suppression system warranty if arranged, shall be covered solely under the third-party supplier's warranty and are excluded from the fabrication warranty.
- \* No warranty provided on painting works.
- \* Delivery services if arranged, shall be covered solely under the third-party supplier's warranty and are excluded from the fabrication warranty.

#### Refund & Termination

- \* All deposits and payments are strictly non-refundable once work has been placed in schedule and production scheduling has been confirmed, regardless of project suspension or cancellation by the client.
- \* In the event of project suspension or cancellation by the client, TAL Trucks Consultancy FZE reserves the right to remove the project from production schedule, issue no refund on deposits or payments made up to the suspension or cancellation.

#### Inspection, Acceptance & Final Payment

- \* The client shall inspect the unit upon completion. Absence of written objections within forty-eight (48) hours shall be deemed full and unconditional acceptance.
- \* Receipt of final payment constitutes conclusive evidence that all works, materials, and finishes have been inspected, accepted, and completed in full compliance with the approved drawings, specifications, and agreed scope.
- \* No claims, disputes, or rectification requests shall be entertained after final payment, unless agreed by TAL Trucks Consultancy FZE and client.